



DEFENSE LOGISTICS AGENCY

DLA Land and Maritime
POST OFFICE BOX 3990
COLUMBUS, OH 43218-3990

16 June 2016

MEMORANDUM FOR MILITARY/INDUSTRY DISTRIBUTION

SUBJECT: Initial Draft of MIL-PRF-83726/13L.
Project number 5945-2016-035.

The draft of the above subject document is being sent to you for review and comments. The draft consists of the following changes:

Revised document to insert Qualification assurance provision to state Group B and group C testing are not required.

If the document is of interest to you, please provide your comments electronically. This can be in the form of a return e-mail, with or without an attached text file. A 30-day coordination cycle from the date of this letter has been allotted. Please provide your comments within that time period. If no comments are received in the allotted 30 day coordination cycle, concurrence is assumed and all comments received after will be held to the first amendment. Since Navy-EC is a custodian for this document; all Navy review activities should forward their comments directly to this Center. If an electronic response is not possible we will still accept comments via letter, facsimile or phone call but only after you have contacted the project officer listed below. The draft document can be found at the following DLA LAND AND MARITIME-VA web page:

<http://www.landandmaritime.dla.mil/Programs/MilSpec/initialdrafts.aspx>

This process still requires military departments to identify their comments as "Essential" or "Suggested". Essential comments must be justified with supporting data. Military review activities should forward comments to their custodians or this office, as applicable, in sufficient time to allow for consolidating the department reply.

If there are any questions, please contact Erika Baker by the preferred method of E-Mail at Erika.Baker@dla.mil or by telephone at commercial 614-692-4481, DSN 850-4481; or by facsimile at 614-692-6939. Our mailing address as a last resort is DLA Land and Maritime-VAT, P.O. Box 3990, Columbus, OH 43218-3990. If you have further questions or concerns you may contact me at Michael.Radecki@dla.mil by telephone at 614-692-0561 or by DSN 850-0561.

/SIGNED/
Yeasvina Afroz (Acting chief)
MICHAEL A. RADECKI
Chief
Electronic Components Branch

NOTE: This draft, dated 16 June, 2016 prepared by DLA-CC, has not been approved and is subject to modification. DO NOT USE PRIOR TO APPROVAL. (Project 5945-2016-035)

INCH-POUND

MIL-PRF-83726/13L
 DRAFT
 SUPERSEDING
 MIL-R-83726/13K
 15 December 2015


PERFORMANCE SPECIFICATION

RELAYS, SOLID STATE, TIME DELAY, (ON OPERATE), TYPE I
 CLASS C, SPST-NO, 300 MILLIAMPERES, FIXED TIME,
 0.05 TO 600 SECONDS, HERMETICALLY SEALED

Inactive for new design after 15 January 1999.
 No superseding document.

This specification is approved for use by all Departments and Agencies of the Department of Defense.

The requirements for acquiring the product described herein shall consist of this specification and [MIL-PRF-83726](#).




Inches	mm	Inches	mm
.018	0.46	.300	7.62
.060	1.5	.42	10.7
.100	2.54	.58	14.7
.28	7.1	.920	23.37

FIGURE 1. Outline dimensions and configuration of relay.



MIL-PRF-83726/13L
DRAFT DATED 16 JUNE 2016



TIMING DIAGRAM

NOTES:

1. Dimensions are in inches.
2. Metric equivalents are given for general information only.
3. Load is connected between B+ and terminal designated LOAD. Delay begins upon application of power to terminals (B+) and (B-). Upon completion of delay period, circuit from load terminal to ground is completed. (B+) and (B-) are shown for reference only; they do not appear on the relay.
4. Unless otherwise specified, tolerance is ± 0.10 (0.25 mm).
5. This is an active pin. Do not connect this pin to any portion of the circuit or ground.

FIGURE 1. Outline dimensions and configuration of relay - Continued.

REQUIREMENTS:

Operational data:

Timing action: Delay-on-operate.

Timing delay: Fixed time, 50 milliseconds to 600 seconds. See [table I](#).

Timing accuracy: ± 10 percent of the nominal timing under all conditions of input voltage and environmental extremes.

Recycle characteristics:

Before time out: A power interruption occurring after the start but before completion of the timing cycle shall be for a duration of 0.5 percent of the nominal time delay or 10 ms, whichever is greater, to ensure a loss in timing no greater than 10 percent.

After time out: A power interruption of 0.5 percent of nominal time delay or 10 ms, whichever is greater, will initiate a new timing cycle with a loss in timing no greater than 5 percent.

MIL-PRF-83726/13L
 DRAFT DATED 16 JUNE 2016

TABLE I. Available time delay relays. [1/](#)

Dash number	Time delay in seconds ±10%	Dash number	Time delay in seconds ±10%
-0500	.05	-1602	16
-1000	.10	-1802	18
-2000	.20	-2002	20
-3000	.30	-2202	22
-5000	.50	-2502	25
-7500	.75	-3002	30
-1001	1.0	-3502	35
-2001	2.0	-4002	40
-3001	3.0	-4502	45
-4001	4.0	-5002	50
-5001	5.0	-5502	55
-6001	6.0	-6002	60
-7001	7.0	-1003	100
-8001	8.0	-2003	200
-9001	9.0	-3003	300
-1002	10	-4003	400
-1202	12	-5003	500
-1402	14	-6003	600

[1/](#) Additional time delay relays within the 0.05 to 600 second delay range are available. To establish Part or Identifying Numbers (PINs) not listed in [table I](#) (see "PIN" herein).

Input data:

Input voltage: 28 V dc nominal; range 18 V dc to 31 V dc.

Duty rating: Continuous.

Current drain: 10 milliamperes maximum, plus load current.

Reverse polarity protection: The timer will not be damaged or operate when input voltage polarity is reversed.

Output data:

Configuration: SPST-NO, solid state switch closure to ground.

MIL-PRF-83726/13L
DRAFT DATED 16 JUNE 2016

Load ratings:

Resistive: 300 milliamperes at 25°C, derated to 100 milliamperes at +125°C. Minimum load current of 10 milliamperes is required.

Inductive: Three [MIL-PRF-39016/6](#) relays or equivalent with 26.5 V dc coil voltage.

Lamp load: Two M6363/8-5 lamps in accordance with [MIL-DTL-6363](#) or equivalent.

Motor load, dc: Not applicable.

Inductive load, ac: Three [MIL-PRF-39016/6](#) relays or equivalent.

Resistive load, ac: Not applicable.

Motor load, ac: Not applicable.

Load suppression: Suppression for inductive loads for output protection is provided within the unit.

Voltage drop: 2.5 volts maximum at -55°C and +25°C, 2.0 volts maximum at +125°C.

Leakage current: 1 microampere maximum at 25°C, 10 microamperes maximum at +125°C.

Continuous current: Not applicable.

Overload: Not applicable.

Electrical data:

Insulation resistance: 1,000 megohms minimum at 500 V dc. [1/](#)

Dielectric withstanding voltage: 500 V rms, 60 Hz, (sea level). [1/](#)

Transients: In accordance with [MIL-STD-704](#) for 28 V dc system (see figure 11).

[1/](#) Measured between all terminals tied together to the case.

MIL-PRF-83726/13L
DRAFT DATED 16 JUNE 2016

Environmental data:

Temperature range: -55°C to +125°C.

Altitude: 80,000 feet.

Shock: 150 g's for 11 ±1 ms half-sine wave.

Vibration (sinusoidal): 10 Hz to 80 Hz at .06 inch DA. 80 Hz to 3,000 Hz at 20 g's.

Vibration scan: Not applicable.

Acceleration: Not applicable.

Seal: Method 112 of [MIL-STD-202](#), condition C.

Solderability: Not applicable.

Physical data:

Dimensions and configuration: See [figure 1](#).

Terminal strength: Bend test not applicable.

Weight: 12 grams maximum.

Verification:

Qualification: Group B and Group C are not applicable.


Conformance: Group A to [MIL-PRF-83726](#) only.

Marking: See [MIL-PRF-83726](#). In addition, relays shall be marked with the Electrostatic Discharge Sensitive (ESDS) identifier as specified in [MIL-STD-1285](#).

Electrostatic discharge (ESD) control program: Applicable (see [MIL-PRF-83726](#)).

MIL-PRF-83726/13L
DRAFT DATED 16 JUNE 2016

Part or Identifying Number (PIN): Consists of the prefix M83726/13-, a four-digit dash number expressed in milliseconds as follows:



Examples

The first three digits of the dash number are significant; the fourth digit is the number of zeros to follow the first three digits. The time delay is expressed in milliseconds and converted to seconds.

M83726/13 - 0500 - 50 millisecond time delay
M83726/13 - 1001 - 1 second time delay
M83726/13 - 6003 - 600 second time delay

| Quality assurance provisions: Group B and group C testing are not required.

NOTE: As of 15 June 1999, [MIL-PRF-83726](#) no longer specifies Quality Levels, but existing order configurations may still include them. Relays with a "W" quality level indicator at the end are interchangeable with relays without a quality level letter.

Referenced documents. In addition to [MIL-PRF-83726](#), this document references the following:

[MIL-DTL-6363](#)
[MIL-STD-202](#)

[MIL-PRF-39016/6](#)
[ASTM-B488](#)

[MIL-STD-1285](#)

[MIL-STD-704](#)

Changes from previous issue. The margins of this specification are marked with vertical lines to indicate where changes from previous issue were made. This was done as a convenience only and the Government assumes no liability whatsoever for any inaccuracies in these notations. Bidders and contractors are cautioned to evaluate the requirements of this document based on the entire content irrespective of the marginal notations and relationship to the previous issue.

MIL-PRF-83726/13L
DRAFT DATED 16 JUNE 2016

Custodians:
Army - AT
DLA - CC

Preparing activity:
DLA - CC

(Project 5945-2016-035)

NOTE: The activities listed above were interested in this document as of the date of this document. Since organizations and responsibilities can change, you should verify the currency of the information above using the ASSIST Online database at <https://assist.dla.mil>.